ENGINEERING DEPARTMENT.

MYSORE RAILWAYS, HASSAN.

Notification dated 14th July 1930.

Notice is hereby given that the sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, on any working day up to 2 P.M., on 4th August 1930, for collecting and Stacking Broken Stone Ballast on Mysore-Arsikere Railway. An approximate estimate of quantities is given in the following Schedule. The quantities are not guaranteed. The work should be completed by the end of May 1931 showing continuous equal monthly progress.

2. Detailed estimate and conditions of schedule agreement, may be seen at the Executive Engineer's Office, at Mysore Railways, Hassan, on all working days, between 11 A.M. and 5 P.M.

2. (a) Not less than 5,000 c ft. should be collected between two Telegraph Posts.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of one rupee.

3. (a) Tenders may be for full quantity or any portion of it.

4. Every tender must be accompanied by a deposit of Rs. 100 (one hundred rupees) in cash as earnest money and should be superscribed "Tenders for Collecting and Stacking Stone Ballast on Mysore-Arsikere Railways" in default of which tenders will be rejected.

5. The earnest money of rejected tenders will be returned as early as possible after the tenders are disposed of and in the case of accepted tender, it would be held as a part of security under clause 4 of the Schedule Agreement referred to.

6. The final acceptance of any tender will rest with the Engineer-in-Chief, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

7 The name of the competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual schedule agreement, in default of which, his tender will be considered as cancelled.

9. Definite rates against each item of work in the Schedule should be noted both in figures and in words.

Schedule.

Item of work	Unit	Quantity	Rate
	C.ft.	C.ft.	Rs.
Collection of broken stone, ballast, quartz or granite to pass through 2" ring including stacking the same to standard heaps of 20' x 5' x 2' or 10' x 5' x 2" free from dust, wherever shown, on prepared platforms, inclusive of all charges within Railway limits	...	...	
Pebbles must on no account be used by quarrying or by field picking.	..	..	
The ballast must be collected at nil points on line and on no account over cuttings of more than 3 feet depth or banks of 3 feet height.	...	...	
Between Hassan and Ambuga	1,000	10,000	
Do Ambuga and Mavinkere	1,000	60,000	
Do Mavinkere and Hole-Narsipur	1,000	30,000	
Do Hole-Narsipur and Mandagere	1,000	20,000	
Do Mandagere and Akkihebbalu	1,000	30,000	
Do Akkihebbalu and Hosa-agrahara	1,000	80,000	
Do Belagola and Mysore	1,000	20,000	

M. RAMAIYA,
Executive Engineer.